

SECTION 025802
TEMPORARY TRAFFIC CONTROLS DURING CONSTRUCTION

1. DESCRIPTION

This specification shall govern all work required for Temporary Traffic Controls during construction. The work shall include furnishing, installing, moving, replacing, and maintaining all temporary traffic controls including, but not limited to, barricades, signs, barriers, cones, lights, signals, temporary detours, temporary striping and markers, flagger, temporary drainage pipes and structures, blue business signs, and such temporary devices as necessary to safely complete the project.

2. MATERIALS

Traffic control devices shall conform to the latest edition of the "Texas Manual on Uniform Traffic Control Devices", unless indicated otherwise on the Traffic Control Plan.

3. METHODS

Sufficient traffic control measures shall be used to assure a safe condition and to provide a minimum of inconvenience to motorists and pedestrians.

If the Traffic Control Plan (TCP) is included in the drawings, any changes to the TCP by the Contractor shall be prepared by a Texas licensed professional engineer and submitted to the City Traffic Engineer for approval, prior to construction. If the TCP is not included in the drawings, the Contractor shall provide the TCP prepared by a Texas licensed professional engineer and submit the TCP to the City Traffic Engineer for approval, prior to construction.

The Contractor is responsible for implementing and maintaining the traffic control plan and will be responsible for furnishing all traffic control devices, temporary signage and ATSSA certified flaggers. The construction methods shall be conducted to provide the least possible interference to traffic so as to permit the continuous movement of traffic in all allowable directions at all times. The Contractor shall cleanup and remove from the work area all loose material resulting from construction operations at the end of each workday.

All signs, barricades, and pavement markings shall conform to the BC standard sheets, TCP sheets and the latest version of the "Texas Manual on Uniform Traffic Control Devices".

The Contractor may be required to furnish additional barricades, signs, and warning lights to maintain traffic and promote motorists safety. Any such additional signs and barricades will be considered subsidiary to the pay item for traffic control. All signs, barricades, and posts will be either new or freshly painted.

The contractor and any traffic control subcontractor must be ATSSA certified for Traffic Control.

A competent person, responsible for implementation of the TCP and for traffic safety, shall be designated by the Contractor.

The name and off-hours phone number of the competent person shall be provided in writing at the Pre-Construction Conference.

The competent person shall be on site, during working hours and on call at all times in the event of off-hour emergency.

The contractor must provide temporary blue sign boards that direct traffic to businesses and driveways during each phase of construction – see example below. The sign boards may be either skid mounted or barrel mounted. The City will assist the contractor in determining which businesses and driveways will receive signage during various construction phases. The provision, installation, and removal of signage will be considered to be subsidiary to the contract items provided for “Traffic Control.”

Example Blue Sign



4. MEASUREMENT AND PAYMENT

Unless otherwise specified on the Bid Form, temporary traffic controls during construction shall be measured as a lump sum. Payment shall include, but not be limited to, furnishing, installing, moving, replacing and maintaining all temporary traffic controls including, but not limited to, barricades, signs, barriers, cones, lights, signals, temporary striping and markers, flaggers, removable and non-removable work zone pavements markings and signage, channelizing devices, temporary detours, temporary flexible-reflective roadway marker tabs, temporary traffic markers, temporary drainage pipes and structures, blue business signs, and such temporary devices and relocation of existing signs and devices. Payment shall be full compensation for all labor, equipment, materials, personnel, and incidentals necessary to provide a safe condition during

construction of all phases and elements of the project and to complete the work.

Payment will be made on the following basis: The initial monthly estimate will include 50% of the lump sum bid amount minus retention (typically 5%). The balance will be paid with the final estimate, upon completion of the project.